

Date – 19-04-2026

To,
Billing Unit – **Sudhir Kumar Gupta**
Donar, Darbhanga
Bihar – 800030

Sub: Offer for Three Phase On-Grid Rooftop Solar Power Plant 40 KW Rooftop System using NON-DCR ½ Cut TOPCon Bifacial PV Modules.

Dear Sir,

We thank you for your enquiry and have pleasure to offer our quotation for the same:

Facilities	Rooftop
Type of Installation	On-Grid Rooftop System
Phase	Three
Estimated Capacity	40 KWp
Preferred Technology	TOPCon – ½ Cut Cell, Bifi
Estimated Energy Generation	58000 – 59000 Units per Year
Solar Array Area	2400 – 2500 Sft
Project Mode	Capex
Project Rationale	Asset for 25 Years

Bill of Material and Make

Sr No	Item	Specification	Make
1	Solar Pv Modules	TOPCon – ½ Cut Cell PV Module with Efficiency > 22.20 % with IS 14286, IS 61215 and IS-61730 certification. Performance Warranty of 25 years (80% module efficiency after 25 years)	Loom Solar / Statcon Energias 575–620 Wp TOPCon Bifi. No. of Panels – 72 600 W × 72 = 43200 W
2	Module Mounting Structure	Hot Dip / Pre-Galvanized / Aluminium / any suitable material with SS nuts and bolts. Designed to withstand wind speed and seismic factors of the site.	MNRE / I.S / Universal Standard / Equivalent
3	Junction Boxes	Dust, Vermin and water proof made from FRP.	MNRE / I.S Standard / Equivalent

REGD. OFFICE

Ranchi

3A Classics, Sarkar Mansion,
Circular Road, Ranchi,
Jharkhand — 834001

BRANCH OFFICE

Patna

C1, Road No. 1, Maurya Vihar
Colony, Khagaul, Patna,
Bihar — 801105

BRANCH OFFICE

Delhi NCR

GF-55, Ashiana Greens,
Indirapuram, Ghaziabad,
Uttar Pradesh — 201010

Sr No	Item	Specification	Make
4	On-Grid Inverter 40 KW	Three Phase String Inverters Ideal for roof top systems complying with all requirements in Die Cast aluminium case, IP66 water proof and dustproof, C5 anti corrosion. High MPP tracking and a wide input voltage range to ensure high levels of efficiency even at low irradiation, to achieve an efficiency of up to 98.3%. With 10 Years of Warranty.	Loom Solar
5	Distribution Boxes, Cables and Accessories	An ACDB/AJB shall be provided in between PCU Load/Grid interface of suitable rating for connection and disconnection of PCU from load. Class 1 Energy Meter for Solar Power monitoring.	Havells / Paraflex / Polycab / Universal

MNC Solar Offer

Item	Capacity (KWp)	Rate/KWp	Total Price
Design, Manufacture, Supply of 40 KWp On-Grid Solar PV System with Solar Module and other Accessories and Connecting cables etc.	40 KWp	48,000/-	19,20,000/-

GST Inclusive	
Total Taxpaid Amount	19,20,000/-
Beneficiary Out Flow Share	19,20,000/-
In Words	Rs. Nineteen lacs Twenty thousand only.

Payment Terms & Conditions

1. 90% Advance along with Confirm Work Order.
2. 10% Upon Installation of 10KWp On-Grid Rooftop Solar Plant.

Schedule of Supply and Installation

The supply and installation will be completed within 10 days from the date of receipt of Contract and Advance.

Note

1. New Smart Meter will be installed in place of old meter in case old meter is post paid.
2. Load will be changed to solar plant load if the load sanctioned is less.

Detailed Scope of Work

REGD. OFFICE

Ranchi

3A Classics, Sarkar Mansion,
Circular Road, Ranchi,
Jharkhand — 834001

BRANCH OFFICE

Patna

C1, Road No. 1, Maurya Vihar
Colony, Khagaul, Patna,
Bihar — 801105

BRANCH OFFICE

Delhi NCR

GF-55, Ashiana Greens,
Indirapuram, Ghaziabad,
Uttar Pradesh — 201010

The scope of work for the installer includes study of the rooftop of buildings, complete design, engineering, manufacture, supply, storage, civil work, erection, testing & commissioning of the grid connected rooftop solar power project as per the norms of the CEA and local DISCOM.

Under Scope of Work will do following activities:

1. Solar Plant Engineering Design.
2. Detailed Planning and Smooth execution of the Project.
3. Supply of the PV Modules, Mounting System and On-Grid Inverter with necessary accessories for On-Site installation. Please note that since Non DCR PV modules are imported, their availability of exact wattage as mentioned in the quotation is challenging. Therefore wattage of 550 to 620 of exactly the same design, technology and company may be installed. This will not affect the efficiency.
4. System installation and commissioning of system.
5. Basic Training on working and Up-keep to Operate and Maintenance staff.
6. System analysis, technical reports and recommendations.
7. NOC/Permission from local DISCOM/Nodal Agencies for connecting SPV power plant to grid.
8. Application for Net Metering Installation and Commissioning.
9. Appropriate AC Cable Length from inverters to the Solar LT Panel placed near to the inverter at appropriate location will be in scope of the installer however AC Cable from Solar LT Panel more than 20 meters will be in scope of client.
10. Company's Warranty for the modules and the Inverter will be provided to the customer.

Assumptions

1. All approvals, NOCs and permissions are in scope of MNC Solar.
2. Any other related work or arrangement like Material Storage location, way for working at roof required for the execution of the installation of the project will be in the scope of Client.
3. Electricity at roof for working will be in the scope of Client.

We assure you to give best services always in time so we are waiting for your valued order.

Your early reply is highly appreciated.

Thanking you,

MNC SOLAR

An ISO 9001:2015 Certified Company
An Authorized PMSG Vendor

BANKING DETAILS

Bank: **Canara Bank**
A/c Number: **120029492096**
A/c Holder Name: **Mahadeva and Company**
IFSC Code: **CNRB0017538**
Branch: Opp. Ratu Block Office, Kathitand, Ratu, Ranchi, Jharkhand

REGD. OFFICE

Ranchi

3A Classics, Sarkar Mansion,
Circular Road, Ranchi,
Jharkhand — 834001

BRANCH OFFICE

Patna

C1, Road No. 1, Maurya Vihar
Colony, Khagaul, Patna,
Bihar — 801105

BRANCH OFFICE

Delhi NCR

GF-55, Ashiana Greens,
Indirapuram, Ghaziabad,
Uttar Pradesh — 201010